

MARYLAND HISTORICAL TRUST CONTINUATION SHEET
U.S. 301 SOUTH CORRIDOR TRANSPORTATION STUDY

Property Name: Woodstock
Survey No.: PG: 82A-13 (PACS A143)

Property Address 8706 S.E. Crain Highway, Upper Marlboro vicinity, Prince George's County
Owner Name/Address Eugene and Mary Sue Couser, 8706 S.E. Crain Highway, Upper Marlboro, MD 20772
Year Built circa 1850

Description:

Woodstock was previously surveyed by the Historic American Building Survey in 1936, by the Maryland-National Capital Park and Planning Commission (M-NCPPC) in 1974, and by the Prince George's County Historic Preservation Commission in 1986. The property was listed on the National Register of Historic Places on September 21, 1987.

National Register Evaluation:

Woodstock, an outstanding example of a mid-nineteenth century plantation house with Greek Revival details, was listed on the National Register of Historic Places on September 21, 1987.

Verbal Boundary Description and Justification:

The boundary of the property consists of 2.02 hectares (5.0001 acres), all of that parcel of land described in Prince George's County deed #4245:414, according to the Maryland Historical Trust Inventory Form prepared in 1986. This parcel incorporates "all of the highest point of land on which the house stands, as well as the ancient holly, linden and red maple immediately east and west of it. The parcel includes also the unpaved drive which leads to the house from U.R. Route 301, and the sloping fields to the south and north, on which stands the twentieth century smoke house. The boundaries of this parcel preserve the immediate grounds of the dwelling and its complete environmental setting."

MHT CONCURRENCE:

Eligibility ☐ recommended ☐ not recommended

Criteria ☐ A ☐ B ☐ C ☐ D Considerations ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G ☐ None

Comments: _____


Reviewer, Office of Preservation Services Date


Reviewer, NR program

Date

Preparer:
P.A.C. Spero & Company
September 1996

PIKE Mellwood
U.S. 301 South Corridor
Transportation Study
Survey # A143, PG:82A-13
Property Name Woodstock
Town/County Upper Marlboro vicinity/Prince George's Co.
Quadrangle Upper Marlboro





PG:82A-13



PG:82A-13



United States Department of the Interior
National Park Service

For NPS use only

National Register of Historic Places Inventory—Nomination Form

received

date entered

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic Woodstock

and or common Woodstock

2. Location

street & number 8706 S. E. Crain Highway (U.S. Route 301) N/A not for publication

city, town Upper Marlboro X vicinity of Fifth Congressional District

state Maryland code 24 county Prince George's code 033

3. Classification

Category	Ownership	Status	Present Use
<u> </u> district	<u> </u> public	<u>X</u> occupied	<u> </u> agriculture
<u>X</u> building(s)	<u>X</u> private	<u> </u> unoccupied	<u> </u> commercial
<u> </u> structure	<u> </u> both	<u> </u> work in progress	<u> </u> educational
<u> </u> site	Public Acquisition	Accessible	<u>X</u> private residence
<u> </u> object	<u> </u> in process	<u> </u> yes: restricted	<u> </u> entertainment
	<u> </u> being considered	<u> </u> yes: unrestricted	<u> </u> government
	<u>X</u> not applicable	<u>X</u> no	<u> </u> industrial
			<u> </u> military
			<u> </u> other:

4. Owner of Property

name Mr. and Mrs. Eugene Couser (Mary Sue)

street & number 8706 S. E. Crain Highway

city, town Upper Marlboro N/A vicinity of state Maryland 20772

5. Location of Legal Description

courthouse, registry of deeds, etc. Prince George's County Courthouse

street & number Main Street

city, town Upper Marlboro state Maryland 20772

6. Representation in Existing Surveys

title Maryland Historical Trust
title Historic Sites Inventory has this property been determined eligible? yes X no

date 1987 federal X state county local

depository for survey records Maryland Historical Trust

city, town Annapolis state Maryland 21401

7. Description

PG: 82A-13

Condition

☒ excellent
☐ good
☐ fair

☐ deteriorated
☐ ruins
☐ unexposed

Check one

☐ unaltered
☒ altered

Check one

☒ original site
☐ moved date

N/A

Describe the present and original (if known) physical appearance

Number of Resources:

Contributing

Non-contributing

1
2
0
0
3

1 buildings
0 sites
0 structures
0 objects
1 Total

Original and historic functions
and uses:

X agriculture
X residential

Number of previously listed National
Register properties included in this
nomination: 0

DESCRIPTION SUMMARY

Woodstock is a gable-roof frame dwelling which stands on a high point of land surrounded by rolling farmland, and bounded on the west by U.S. Route 301. The house consists of a two-and-one-half story main block with exterior gable-end chimneys, built in the mid-nineteenth century, and a one-and-one-half-story wing. The westerly two bays of this five-bay wing, enclose an earlier freestanding building, a remnant of the older Timberly plantation; it is now connected to the main block by a later three-bay connecting link or hyphen. The house has simple but handsome interior trim, in the Greek Revival style, and has been recently and carefully restored. There are remnants of two old buildings just west of the house, and a twentieth century smoke house on the slope to the north.

United States Department of the Interior
National Park Service

PG:82A-13

National Register of Historic Places
Continuation SheetSection number 7 Page 1Woodstock
Prince George's County, Maryland

DESCRIPTION

Woodstock is a gable-roof frame dwelling which consists of a two-and-one-half-story main block, with a two-part, one-and-one-half-story wing. It stands on a high point of land surrounded by rolling farmland, and overlooks U.S. Route 301 to the west. The main block is side gabled, 28 by 34 feet, three bays by two bays. Entrance is in the third bay of the main south facade through an eight-panel door (six small panels over two large ones) flanked by full-length green louvered shutters. A one-story hip-roof porch shelters this main south facade; it is supported by square posts with molded capitals and bases, embellished by large jig-sawn brackets, and rests on a concrete foundation. A rear door in the first bay of the north facade has six panels.

The siding of the main block is plain horizontal board with plain corner posts, all painted white. Windows are wood frame double hung sash with six lights over six, and narrow molded surrounds, and have dark green louvered shutters. The plain board cornice has crown molding and is slightly flared at the eaves, and is slightly flared at the eaves, and is not returned at the gable ends. The gable roof is covered with gray asphalt shingle. There are two (unmatched) tall exterior brick chimneys at the west gable end. Between the two stacks at third level is a small four over four window; in the corresponding position in the east gable end are two four over 4 windows. These stacks are laid in American bond, four courses of stretchers to one of headers. The southerly stack has weatherings above the second story, and has been widened by the addition of new brick, to accommodate a new heating system. The narrow northerly stack has no weatherings, and is enclosed at first story by the attached kitchen wing. The main block rests on a brick foundation which encloses a basement under the south half of the building; from this basement space, one can see the large hand-hewn sill beams, joined with mortise and tenon. Access to the basement is through a bulkhead between the two chimneys. A builder's trench is clearly visible just outside (north) of the north foundation wall of the basement.

Interior plan of the main block consists of side stair hall and connecting double parlors. The open string two-run staircase rises along the east (exterior) wall of the stairhall, then turns 90 degrees at a landing and reverses to the second floor. It has plain square balusters and a simple round rail. In place of a newel post is a plain carved post. The staircase has a paneled spandrel, and plain bracketed stair ends. The center section of each riser is painted black, as suggested by early layers of paint.

See Continuation Sheet No. 2

United States Department of the Interior
National Park Service

PG:82A-13

National Register of Historic Places Continuation Sheet

Section number 7 Page 2

Woodstock
Prince George's County, Maryland

Two doorways lead from the stairhall westward into the two adjoining parlors. These parlors are connected by double doors which were folded back into the north parlor (dining room). Each leaf of the double door, like the principal south entrance door, has six small panels over two large ones. Identical wooden mantels frame the fireplaces in the two parlors: the mantel frieze has a rounded "pillow" projection, which is repeated (vertically) in the pilasters which flank the firebox.

Surrounds of doors and windows consist of an inner bead, broken (two-step) field and outer molding. Baseboards are molded; there are no molded cornices or chair rails. All interior doors in the main block hang on mid-nineteenth century "Baldwin" hinges. The lock-box on the main (south) door is marked "I. Walker VR".

Mantels in the bedrooms above the two parlors are identical to those in the parlors.¹ Moldings on the second story are similar to those on the first, but have an unbroken (one-stop) field. The staircase continues to the third floor. The second story north window which lights the stairhall is split by the landing between second and third floors.

Extending west from the main block and flush with its north facade, is a one-and-one-half-story two part kitchen wing, 16 by 30 feet. Construction details indicate that the westerly section is the oldest, and that the central or easterly section of the wing was later built as a hyphen to connect the older building to the main block.

The westerly (older) section of the wing (16 by 14 1/2 feet) is two bays wide with entrance in the second bay of its facade through a modern door (four small lights over four panels). There is a corresponding rear door on the north facade, which opens onto a high concrete stoop.² This small building rests on whole logs and has a very shallow crawl space underneath. From the upper-story room in the hyphen, one can observe the original exterior wide, hand-split board siding of the east gable end of the older building. Floor boards are wide and probably original; the framing is reinforced with brick

¹During restoration work in the 1970s, the mantel was removed from the south bedroom and installed in the dining room, the only room from which the mantel was missing. A new mantel was made for the south bedroom, identical to the other three.

²In the early twentieth century, a rear shed porch on the north facade of the wing had been enclosed to form a kitchen. This enclosed porch was removed during the restoration work of the 1970s, and the concrete stoop was constructed at that time.

United States Department of the Interior
National Park Service

PG:82A-13

National Register of Historic Places Continuation Sheet

Section number 7 Page 3

Woodstock
Prince George's County, Maryland

nogging. Just south of the ridge at the west gable end is an exterior freestanding brick chimney, four courses of stretchers to each course of headers, with weatherings above the first story level.

This small structure is now joined to the main block by a three-bay-wide hyphen (16 by 15 1/2 feet), of the same depth as the older building. The hyphen is now used as a kitchen, while the older westerly section has been converted into a family room, and is paneled with narrow beaded wainscoting. A boxed staircase rises between the two sections, giving access to two small rooms, one above each section, connected by a batten door. Each of these rooms is lighted by a gable dormer on the south. Each dormer encloses a 6/6 window, has a molded cornice, and is sided with diagonal boards.

The two sections join to form a four-bay wing, 16 by 30 feet, sided with plain horizontal boards, narrower than those of the main block, all painted white. Windows are 6/6 double hung sash with plain board surrounds, and have dark green louvered shutters. There is a second door in the fourth bay of the south facade (second bay of the hyphen); it has one large pane of glass over three molded panels. The roof of the wing is covered with wooden shingles; it has a molded cornice, flared at the eaves like that of the main block. A one-story shed-roof porch, continues from the roofline to shelter the entire south facade of the wing. The porch is supported by plain square posts, and has a brick floor. The wing rests on a brick foundation topped by one course of rowlock, and encloses a shallow crawl space.

Woodstock stands on the highest point of land on a 5-acre parcel which was carved out of the original 320-acre farm. An unpaved drive leads east to the house from U.S. Route 301, which is the western boundary of the property. (The historic access to the house was from the old road to the east.) The drive ends just east of the house in a circle which encloses a large evergreen tree; a short distance northeast of the circle stands a very large holly, estimated to be 185 years old. Circa 20 feet southwest of the kitchen wing stands a massive red maple, estimated to be 210 years old. A linden tree near the west end of the house is also of great age, and is being evaluated for champion status.

The immediate grounds of the house are bounded by a rail fence in the north and west, and a split rail (snake) fence on the south; the fields outside these boundaries are devoted to sheep grazing. On the sloping ground in the field to the north is a twentieth century smoke house, gable-roofed with concrete block foundation. It has replaced an older smoke house which stood on a brick foundation still visible in the yard west of the house. Directly west of the house is a small square herb garden which marks the spot where an ice house once stood.

8. Significance

PG:82A-13

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates ca.1850 and earlier Builder Architect unknown

Statement of Significance (in one paragraph)

Applicable Criteria: C

Applicable Exceptions: none

Significance Evaluated: local

SIGNIFICANCE

Woodstock is an outstanding example of a mid-nineteenth century plantation house with decorative elements in the Greek Revival style. The main block was probably built in the early 1850s by Washington Custis Calvert of Mount Airy; it was subsequently attached by means of a connecting hyphen to an older kitchen building on the property. In 1860 Woodstock became the home of James Beall Belt retired Clerk of the Prince George's County Court, and passed after his death to his son John W. Belt, who served also as Clerk of the Court. Woodstock exemplifies a house style typical of successful small plantations of the period; it is one of only three surviving examples in Prince George's County of this once popular Tidewater house style. It is in excellent condition and stands in a prominent location in functioning farmland, a visible landmark overlooking a much travelled highway. It is an important example of Prince George's County nineteenth century architectural history.

United States Department of the Interior
National Park Service

PG:82A-13

National Register of Historic Places Continuation Sheet

Section number 8 Page 4

Woodstock
Prince George's County, Maryland

HISTORY AND SUPPORT

Woodstock stands on a tract known as Timberly, patented by Robert Ridgely in 1672.³ Part of this tract, adjoining the tract called "Croom", belonged in the late eighteenth and early nineteenth centuries to Edward Scott. Scott's dwelling was on the Croom tract, but several farm buildings, including a small kitchen, stood on Timberly, which adjoined Croom on the west.⁴

A 220 acre portion of Timberly, known as the Woodstock farm, passed to Scott's son, Horatio C. Scott, a prominent merchant in the village of Upper Marlboro. After Edward Scott died in 1851, Horatio C. Scott (who lived in the old Wardrop House, PG #79-28, sold the Woodstock farm (in 1853) to Washington Custis Calvert, one of the seven sons of Edward H. Calvert of Mount Airy. Washington Calvert had married in 1851, and had received in trust 100 acres of Mount Airy which adjoined Scott's Timberly. It is almost certain that it was Calvert who built the main block of the house at Timberly as his home.⁵

The new house was typical of small plantation houses of the mid-nineteenth century; it consisted of a side stairhall and double parlors, warmed by fireplaces on the exterior wall. The trim of the house was plain, but handsome, Greek Revival style, with broken field moldings, and carved "pillow" projections highlighting the wooden mantels. A pre-existing kitchen building, with boxed staircase and sleeping loft above, was put to use by Calvert; it stood 15 feet from his new dwelling.

Washington Calvert lived only a short time in this house. His wife died in 1857, and in 1860 he sold his entire farm (220 acres of Timberly and 100 adjoining acres of Mt. Airy) to James Beall Belt, retired Clerk of the County Court. Calvert remarried and (apparently) left Prince George's County.⁶

³Patents, #16:496.

⁴Federal Direct Tax for Prince George's County, 1798.

⁵Prince George's County Estate file #174; will PC #1:443, Wollon, J. T., and Pearl, S. G., **Historic Structures Report**, Buck-Wardrop House, PG #79-28; Prince George's County Deeds ON #1:467; CSM #3:345, 346; Prince George's County Marriage Licenses; Census for Prince George's County, 1840, 1850.

⁶Prince George's County Deeds CSM #3:366; **Stones and Bones**, Cemetery Records of Prince George's County, Maryland, 1984, p. 29.

United States Department of the Interior
National Park Service

PG:82A-13

National Register of Historic Places Continuation Sheet

Section number 8 Page 5 Woodstock
Prince George's County, Maryland

James Beall Belt had served as Clerk of the Court from 1838 to 1851. He owned a house and lot in Upper Marlboro where he resided, and also a store house, granary and office where he operated a mercantile business. His wife had died in 1859, and in the following year he moved with his son, John W. Belt, into Washington Calvert's house on Timberly which he renamed Woodstock. Belt continued to operate the granary, store house and office in Upper Marlboro, trading as James B. Belt and Son.⁷

After the Civil War, Belt fell into financial difficulties; he mortgaged and remortgaged his Woodstock farm. His financial difficulties were still unresolved at the time of his death in 1882. By his will he devised all of his estate, "the farm on which I now reside called Woodstock, together with all stock, crops, utensils, machinery then upon it, also all lots in Upper Marlboro, and all interest in the mercantile business carried on under the name of James B. Belt and Son," to his son, John Williamson Belt and his wife, Mary D. Belt, for their lives, in trust for his grandson (their son), James B. Belt.⁸

In the year of his father's death, John W. Belt was appointed to his father's former position as Clerk of the Court, a position which he held until his death in 1896. He also turned over the management of his store house, granary and office in Upper Marlboro to Hamilton Hall, and moved his family from their town dwelling to his father's house at Woodstock. He was also able to settle the liens on the Woodstock property by offering it for sale (by decree of the Equity Court) and purchasing it himself. It was advertised at this time (1889) as "320 acres, the land now occupied by John W. Belt, improved by a large and comfortable dwelling house and all necessary barns and out-buildings."⁹

⁷Prince George's County Court Records March 28, 1838; Prince George's County Tax Assessments, 1830s-1860s; **Stones and Bones**, p. 118.

⁸Prince George's County Deed WAJ #2:585 (mortgage); Prince George's County Will WAJ Jr. #1:257.

⁹Prince George's County Equity #1794; Prince George's County Deed JWB #12:742, 744.

United States Department of the Interior
National Park Service

PG:82A-13

National Register of Historic Places Continuation Sheet

Section number 8 Page 6 Woodstock
Prince George's County, Maryland

John W. Belt died in 1896, and was buried with his parents at Trinity Church, Upper Marlboro. His estate was administered by his brother-in-law, attorney Caleb Clark Magruder (II), and Woodstock was conveyed to his son, James B. Belt. The younger Belt predeceased his mother, however, and consequently Woodstock was devised by her will (1924) to her nephew, Caleb Clarke Magruder III. It remained Magruder's home until his death in the 1940s.¹⁰

When the present owners purchased Woodstock from the Magruder family in 1973, the house had stood vacant and boarded up for several years, and was in deteriorating condition. The new owners undertook major restoration work, removing the shed porch which had served as a kitchen, and installing a new kitchen in the hyphen. The house is now in excellent condition, and is a prominent and visible landmark high on a hill east of U.S. Route 301. Woodstock is a significant example of a mid-nineteenth century plantation house style of southern Prince George's County, of which only a few survive.¹¹

¹⁰Stones and Bones, p. 119; Prince George's County Estate File #1633, Prince George's County Deed JB #1:393; Prince George's County Will WTD #1:35.

¹¹Prince George's County Deed #4245:414. Recent survey work in Prince George's County has identified only two other buildings of similar plan: Bellevue (84-20), and the Turner House (87B-5). To each of these houses there is attached lower kitchen wing which partially covers the exterior brick chimneys. In the case of the Turner House, the kitchen is a considerably later addition. Six other mid-nineteenth century dwellings [Beuna Vista (70-17), Solitude (77-5), the Nourse House (77-11), the Coftren House (86A-10), the Plantation (86A-16) and Kalaird (86B-9)] are similar to Woodstock, but have interior chimneys and/or alterations which have significantly changed the lines of the building.

United States Department of the Interior
National Park Service

PG:82A-13

National Register of Historic Places
Continuation Sheet

Section number 8 Page 7

Woodstock
Prince George's County, Maryland

CHAIN OF TITLE

WOODSTOCK - P.G. #82A-13

- #4245:414 - 7/5/1973 - Deed Mittie H. Magruder, widow, to Eugene and Mary Sue Couser, 5.001 acres (with 60 foot right-of-way) of land in Melwood District which grantor acquired by Will WDA #11:169.
- WDA #11:169 - 10/15/1962 - Will Testator, Mercer Hampton Magruder: devises to wife Mittie Hall Magruder; to daughters, Florence Hall Magruder and Mary Belt Magruder Vickery; to sons Alexander Clarke Magruder and Mercer Hampton Magruder, Jr. Woodstock farm, 310 acres, to wife Mittie Hall Magruder who is also appointed executrix.
- #1147:491 - 8/15/1949 - Will Mary Belt Magruder, unmarried, to M. Hampton Magruder, St., 200 acres of Timberly and 100 acres of Mount Airy adjoining which grantor acquired from C. C. Magruder by #620:323, the same land described in JB #1:393 and JWB #12:744.
- #620:323 - 9/30/1941 - Deed Caleb C. Magruder to Mary Belt Magruder (niece of grantor, and daughter of M. Hampton Magruder) for natural affection, the land which grantor acquired by Mary D. Belt's Will WTD #1:35, same land described in JB #1:393 (1898) and in mortgage JWB #12:744 (1890).
- WTD #1:35 - 6/26/1924 - Will Testator, Mary D. Belt; devises to sister Bettie R. Magruder and niece Mildred W. N. Bowling; to nephew Caleb C. Magruder, Jr. "the farm I now reside on, Woodstock, with entire contents of the dwelling house there", also farm implements, horses, cattle, crops, etc. C. C. Magruder, Jr., appointed executor.

United States Department of the Interior
National Park Service

**National Register of Historic Places
Continuation Sheet**

Section number 8 Page 8

Woodstock
Prince George's County, Maryland

JB #1:393 - 3/18/1898 - Deed

John A. Barker, attorney, of Baltimore, to James B. Belt; at public sale, February 1898, Barker, attorney in mortgage (JWB #12:744), sold land of John W. Belt after default in payment, to James B. Belt, high bidder at \$6,150. Lands include 320-1/2 acres of land on the road from Upper Marlboro to Brandywine, the farm on which John W. Belt resided at time of his death, and upon which James B. Belt, the grantee, now resides (also store lot of James B. Belt and son in Marlboro, and parsonage property).

#1633 - 1897 - Estate File

John W. Belt died intestate, 1897, leaving widow Mary D. Belt and son James B. Belt.

JWB- #12:744 -1/9/1890 - Mortgage

John W. and Mary D. Belt to Elizabeth Bose of Baltimore. Bose has lent to mortgagors \$5,500; to secure payment, the Belts mortgage to her 200 acres of Timberly and 100 acres of Mount Airy (same described in CSM #3:366), also parsonage lot in Marlboro, and storehouse/granary/office lot in Marlboro of James B. Belt and son, all of which had been mortgaged to William B. Bowie in 1881, and conveyed to John W. Belt by JWB #12:742.

JWB- 12:742 - 1/9/1890 - Deed

Joseph S. Wilson, trustee in Equity 1794, to John W. Belt at public sale (December 1889) where Belt was high bidder at \$6,000 (Wilson appointed to sell land after default in mortgage from James B. Belt to William B. Bowie: parsonage lot and storehouse lot in Marlboro, land at Rosaryville; and farm near Rosaryville upon which James B. Belt resided at the time of his death and where John W. Belt now resides, 220 acres of timberly and 100 acres of Mount Airy.

United States Department of the Interior
National Park Service

**National Register of Historic Places
Continuation Sheet**

Section number 8 Page 9

Woodstock
Prince George's County, Maryland

#1734 - 1889/90 - Equity

Sale of land of James B. Belt, deceased, after foreclosure of mortgage (from James B. Belt to William B. Bowie, 1881; mortgage assigned to John W. Belt 1883 by widow of William B. Bowie). Several properties including "320 acres, land now occupied by John W. Belt, improved by a large and comfortable dwelling house, and all necessary barns and outbuildings."

WAJ - #1:257 - 7/18/1882 - Will

James B. Belt, testator: all estate, "the farm on which I reside called Woodstock, together with all stock, crops, utensils, machinery, etc., all lots in Upper Marlboro, all interest in mercantile business carried on under name of James B. Belt and Son", to son John W. Belt and his wife Mary D. Belt for their lives, in trust for my grandson, James B. Belt.

WAJ #2:585 - 5/11/1881 - Mortgage

James B. and John W. Belt (in debt to William B. Bowie \$3,000) to said Bowie, lots in Marlboro and farm, parts of Timberly and Mount Airy as described in mortgage HB #13:374. This mortgage assigned to John W. Belt in 1883 by Ann H. Bowie, executrix of William B. Bowie.

HB #13:374 - 5/9/1878 - Mortgage

James B. Belt of P. G. to Samuel B. Hance, 220 acres of Timberly and 100 acres of Mount Airy, same which Belt acquired by CSM #3:366 (beginning at a stone on the west side of the road from Rantin's to Upper Marlboro, the stone being the boundary of the land of Benjamin Duvall, deceased, up the road to the gate leading to the land of the late Polydore E. Scott; this mortgage to secure payment of \$5,000 debt owned to Hance by James B. and John W. Belt.

United States Department of the Interior
National Park Service

PG:82A-13

National Register of Historic Places Continuation Sheet

Section number 8 Page 10

Woodstock
Prince George's County, Maryland

CSM #3:366 - 2/16/1860 - Deed

Washington C. Calvert of P.G. to James B. Belt for \$10,000.

- (1) 220 acres of timberly which Calvert acquired in 1853 from Horatio Scott by ON #1:467.
- (2) 100 acres of Mount Airy contiguous of Timberly, which Calvert acquired in January 1860 from Cecilius B., Eleanor A. and John Calvert.

CSM - #3:346 - 1/25/1860 - Deed

Cecilius, Eleanor and John Calvert to Washington C. Calvert for \$20,000, 100 acres of Mount Airy, in trust to Cecilius by George Calvert by AB #10:510 in 1836, same described in CSM #3:345.

CSM - #3:345 - 1/23/1860 - Deed

Washington C. Calvert to Eleanor and Cecilius Calvert for \$5,521, all of Washington C. Calvert's interest in 100 acres of Mount Airy.

ON - #1:467 - 11/10/1853 - Deed

Horatio C. and Henrietta M. Scott for P. G. to Washington C. Calvert of P. G. for \$11,028.63; 220 acres of Timberly, beginning on the road at Benjamin Duvall's north to the entrance to P.E. Scott's land, southeast to the Southwest Branch, then southeast, then west on Liver's Branch to the beginning.

United States Department of the Interior
National Park Service

PG:82A-13

National Register of Historic Places Continuation Sheet

Section number 10 Page 11 Woodstock
Prince George's County, Maryland

VERBAL BOUNDARY DESCRIPTION AND JUSTIFICATION

The nominated property consists of 5.001 acres, all of that parcel of land described in Prince George's County deed #4245:414. This parcel includes all of the highest point of land on which the house stands, as well as the ancient holly, linden and red maple immediately east and west of it. The parcel includes also the unpaved drive which leads to the house from U.S. Route 301, and the sloping fields to the south and north, on which stands the twentieth century smoke house. The boundaries of this five-acre parcel preserve the immediate grounds of the dwelling, and its complete environmental setting.

Boundary Description: Beginning for the same at an iron pipe set in the eastern right-of-way of U.S. 301 (250' wide) said pipe being further located as being the following courses and distances from the intersection of said eastern right-of-way and the 39th line or North 61° 28' 29" West 1865.95 foot line of the Fred Spinks, et ux., property as recorded among the Land Records of Prince George's County, Maryland in Liber 2263, folio 382, said line being a boundary between the said Spinks property and the property of Mittie H. Magruder as recorded among the Land Records of Prince George's County, Maryland in Liber 1147, folio 491; with the said eastern right-of-way of U.S. 301 North 24° 18' 34" East 8.14 feet to a point of curvature, thence with the arc of a curve to the left 1211.94 feet, having a radius of 14499.95 feet and being scribed by a chord North 21° 54' 54" East 1211.58 feet to a point of tangency, North 19° 31' 14" East 492.21 feet to an iron pipe set, said point being the aforementioned point of beginning; THENCE leaving said place of beginning so fixed and binding with the said eastern right-of-way of U.S. 301 North 19° 31' 14" East 124.49 feet to an iron pipe set; THENCE leaving said eastern right-of-way of U.S. 301 and running for new lines of division through the abovementioned land of Mittie H. Magruder the following four (4) courses and distances: South 74° 26' 33" East 592.70 feet to an iron pipe set, South 19° 31' 14" West 441.27 feet to an iron pipe set, North 66° 33' 59" West 512.48 feet to an iron pipe set, and North 19° 31' 14" East 240.84 feet, also with the end of a 60 foot right-of-way to an iron pipe set on the northern side of the said 60 foot right-of-way, for use in common with the herein described property and the remainder of the said Magruder property; THENCE with the northern side of the said 60' right-of-way North 70° 28' 46" West 80.00 feet to the place of beginning.

CONTAINING 5.0001 acres, more or less, as surveyed by J. R. McCrone, Jr., Inc., Registered Professional Engineers and Land Surveyors in June 1973.

BEING a part of the property of Mittie H. Magruder, as recorded among the Land Records of Prince George's County, Maryland in Liber 1147, folio 491.

9. Major Bibliographical References

PG:82A-13

See footnotes in Sections 7 and 8.

10. Geographical Data

Acreage of nominated property 5.0001 acresQuadrangle name Upper Marlboro, MD, Section HQuadrangle scale 1:24000

UTM References

A

1	8	3	4	3	4	6	0	4	2	9	2	5	2	0
Zone		Easting				Northing								

B

Zone		Easting				Northing								

C

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification

See Continuation Sheet No. 11

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
N/A			

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Susan G. Pearl, Principal Investigator, Historic Survey ProjectPrince George's Countyorganization Historic Preservation Commissiondate September 1986

c/o County Planning Division M-NCPPC

street & number 14741 Gov. Oden Bowie Drivetelephone (301) 952-3521city or town Upper Marlborostate Maryland 20772

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

 national state X local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature 8-4-87

title

date

For NPS use only

I hereby certify that this property is included in the National Register


date

Keeper of the National Register

Attest:

date

Chief of Registration




WOODSTOCK

PG:82A-13

Prince George's County
Maryland

sketch plan, 1986

1" = 200'



Woodstock
PG: 82A-13

Prince George's Co
Maryland

18/343400/4292520

Magi No.

DOE yes no

Maryland Historical Trust

State Historic Sites Inventory Form

1. Name (indicate preferred name)

historic Woodstock

and/or common

2. Location

street & number 8706 S.E. Crain Highway not for publicationcity, town Upper Marlboro vicinity of congressional district 5state Maryland county Prince George's

3. Classification

Category	Ownership	Status	Present Use
<u> </u> district	<u> </u> public	<u> </u> occupied	<u> </u> agriculture
<u>X</u> building(s)	<u>X</u> private	<u> </u> unoccupied	<u> </u> commercial
<u> </u> structure	<u> </u> both	<u> </u> work in progress	<u> </u> educational
<u> </u> site	Public Acquisition	Accessible	<u> </u> entertainment
<u> </u> object	<u> </u> in process	<u> </u> yes: restricted	<u> </u> government
	<u> </u> being considered	<u> </u> yes: unrestricted	<u> </u> industrial
	<u>X</u> not applicable	<u>X</u> no	<u> </u> military
			<u> </u> museum
			<u> </u> park
			<u>X</u> private residence
			<u> </u> religious
			<u> </u> scientific
			<u> </u> transportation
			<u> </u> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Eugene and Mary Sue Couserstreet & number 8706 S.E. Crain Highway telephone no.: city, town Upper Marlboro, state and zip code Maryland 20772

5. Location of Legal Description

courthouse, registry of deeds, etc. Prince George's County Courthouse liber 4245street & number Main Street folio 414city, town Upper Marlboro, state Maryland

6. Representation in Existing Historical Surveys

title Historic American Buildings Survey/P.G. County Inventory of Historic Sitesdate 1936/1974 X federal state X county localdepository for survey records Library of Congress/P.G. County Historic Preservation Commissioncity, town Upper Marlboro, state Maryland 20772

7. Description

Survey No. P.G. #82A-13

Condition

☒ excellent
☐ good
☐ fair

☐ deteriorated
☐ ruins
☐ unexposed

Check one

☐ unaltered
☒ altered

Check one

☒ original site
☐ moved date of move _____

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Summary Description

Woodstock is a gable-roof frame dwelling which stands on a high point of land surrounded by rolling farmland, and bounded on the west by U.S. Route 301. The house consists of a two-and-one-half story main block with exterior gable-end chimneys, built in the mid-nineteenth century, and a one-and-one-half-story wing. The westerly two bays of this five-bay wing, enclose an earlier freestanding building, a remnant of the older Timberly plantation; it is now connected to the main block by a later three-bay connecting link or hyphen. The house has simple but handsome interior trim, in the Greek Revival style, and has been recently and carefully restored. There are remnants of two old outbuildings just west of the house, and a twentieth century smoke house on the slope to the north.

Description

Woodstock is a gable-roof frame dwelling which consists of a two-and-one half story main block, with a two-part one-and-one-half story wing. It stands on a high point of land surrounded by rolling farmland, and overlooks U.S. Route 301 to the west. The main block is side gabled, 28 by 34 feet, three bays by two bays. Entrance is in the third bay of the main south facade through an eight-panel door (six small panels over two large ones) flanked by full-length green louvered shutters. A one-story hip-roof porch shelters this main south facade; it is supported by square posts with molded capitals and bases, embellished by large jig-sawn brackets, and rests on a concrete foundation. A rear door in the first bay of the north facade has six panels.

The siding of the main block is plain horizontal board with plain corner posts, all painted white. Windows are 6/6 double hung sash with narrow molded surrounds, and have dark green louvered shutters. The plain board cornice has crown molding and is slightly flared at the eaves, and is not returned at the gable ends. The gable roof is covered with gray asphalt shingle. There are two (unmatched) tall exterior brick chimneys at the west gable end. Between the two stacks at third level is a small 4/4 window; in the corresponding position in the east gable end are two 4/4 windows. These stacks are laid in American bond, four courses of stretchers to one of headers. The southerly stack has weatherings above the second story, and has been widened by the addition of new brick, to accommodate a new heating system. The narrow northerly stack has no weatherings, and is enclosed at first story by the attached kitchen wing. The main block rests on a brick foundation which encloses a basement under the south half of the building; from this basement space, one can see the large hand-hewn sill beams, joined with mortise and tenon. Access to the basement is through a bulkhead between the two chimneys.

8. Significance

Survey No. P.G. #82A-13

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates ca. 1800, ca. 1853 Builder/Architect

check: Applicable Criteria: ☐ A ☐ B ☒ C ☐ D
and/or

Applicable Exception: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Level of Significance: ☐ national ☐ state ☐ local

Prepare both a summary paragraph of significance and a general statement of history and support.

Significance

Woodstock is an outstanding example of a mid-nineteenth century plantation house with decorative elements in the Greek Revival style. The main block was built in the early 1850's by Washington Custis Calvert of Mount Airy; it was subsequently attached by means of a connecting hyphen to an older kitchen building on the property. In 1860 Woodstock became the home of James Beall Belt retired Clerk of the Prince George's County Court, and passed after his death to his son John W. Belt, who served also as Clerk of the Court. Woodstock exemplifies a house style typical of successful small plantations of the period; it is one of only three surviving examples in Prince George's County of this once popular Tidewater house style. It is in excellent condition and stands in a prominent location in functioning farmland, a visible landmark overlooking a much travelled highway. It is an important example of Prince George's County nineteenth century architectural history.

History and Support

Woodstock stands on a tract known as Timberly, patented by Robert Ridgely in 1672¹. Part of this tract, adjoining the tract called "Croom", belonged in the late eighteenth and early nineteenth centuries to Edward Scott. Scott's dwelling was on the Croom tract, but several farm buildings, including a small kitchen, stood on Timberly, which adjoined Croom on the west.²

A 220 acre portion of Timberly, known as the Woodstock farm, passed to Scott's son, Horatio C. Scott, a prominent merchant in the village of Upper Marlboro. After Edward Scott died in 1851, Horatio C. Scott (who lived in the old Wardrop House, PG #79-28, sold the Woodstock farm (in 1853) to Washington Custis Calvert, one of the seven sons of Edward H. Calvert of Mount Airy. Washington Calvert had married in 1851, and had received in trust 100 acres of Mount Airy which adjoined Scott's Timberly. It is almost certain that it was Calvert who built the main block of the house at Timberly as his home.³

9. Major Bibliographical References

Survey No. P.G. #82A-13

Cf. Notes, Item #8

10. Geographical Data

Acreage of nominated property 5 acres

Tax Map 118, Parcel 106

Quadrangle name Upper Marlboro, Section H

Quadrangle scale _____

UTM References do NOT complete UTM referencesA

Zone	Easting							Northing	

B

Zone	Easting							Northing	

C

--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification

Cf. Metes and Bounds

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Susan G. Pearl, Principal Investigator, Historic Survey ProjectPrince George's Countyorganization Historic Preservation Commissiondate September 1986c/o County Planning Division, M-NCPPCstreet & number 14741 Gov. Oden Bowie Drivetelephone 952-3521city or town Upper Marlboro,state Maryland 20772

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

Interior plan of the main block consists of side stair hall and connecting double parlors. The open string two-run staircase rises along the east (exterior) wall of the stairhall, then turns 90 degrees at a landing and reverses to the second floor. It has plain square balusters and a simple round rail. In place of a newel post is a plain carved post. The staircase has a panelled spandrel, and plain bracketed stair ends. The center section of each riser is painted black, as suggested by early layers of paint.

Two doorways lead from the stairhall westward into the two adjoining parlors. These parlors are connected by double doors which are folded back into the north parlor (dining room). Each leaf of the double door, like the principal south entrance door, has six small panels over two large ones. Identical wooden mantels frame the fireplaces in the two parlors: the mantel frieze has a rounded "pillow" projection, which is repeated (vertically) in the pilasters which flank the firebox.

Surrounds of doors and windows consist of an inner bead, broken field and outer molding. Baseboards are molded; there are no molded cornices or chair-rails.

Mantels in the bedrooms above the two parlors are identical to those in the parlors.¹ Moldings on the second story are similar to those on the first, but have an unbroken field. The staircase continues to the third floor. The second story north window which lights the stairhall is split by the landing between second and third floors.

Extending west from the main block and flush with its north facade, is a one-and-one-half-story two-part kitchen wing, 16 by 30 feet. Construction details indicate that the westerly section is the oldest, and that the central or easterly section of the wing was later built as a hyphen to connect the older building to the main block.

The westerly (older) section of the wing (16 by 14 1/2 feet) is two bays wide with entrance in the second bay of its south facade through a modern door (four small lights over four panels). There is a corresponding rear door on the north facade, which opens onto a high concrete stoop.² This small building rests on whole logs and has a very shallow crawl space underneath. From the upper-story room in the hyphen, one can observe the original exterior wide, hand-split board siding of the east gable end of the older building. Floor boards are wide and probably original; the framing is reinforced with brick nogging. Just south of the ridge at the west gable end is an exterior freestanding brick chimney, four courses of stretchers to each course of headers, with weatherings above first story level.

This small structure is now joined to the main block by a three-bay-wide hyphen (16 by 15 1/2 feet), of the same depth as the older building. The hyphen is now used as a kitchen, while the older westerly section has been converted into a family room, and is panelled with narrow beaded wain-

scoting. A boxed staircase rises between the two sections, giving access to two small rooms, one above each section, connected by a batten door. Each of these rooms is lighted by a gable dormer on the south. Each dormer encloses a 6/6 window, has a molded cornice, and is sided with diagonal boards.

The two sections join to form a four-bay wing, 16 by 30 feet, sided with plain horizontal boards, narrower than those of the main block, all painted white. Windows are 6/6 double hung sash with plain board surrounds, and have dark green louvered shutters. There is a second door in the fourth bay of the south facade (second bay of the hyphen); it has one large pane of glass over three molded panels. The roof of the wing is covered with wooden shingles; it has a molded cornice, flared at the eaves like that of the main block. A one-story shed-roof porch, continues from the roofline to shelter the entire south facade of the wing. The porch is supported by plain square posts, and has a brick floor. The wing rests on a brick foundation topped by one course of rowlock, and encloses a shallow crawl space.


Woodstock stands on the highest point of land on a 5-acre parcel which was carved out of the original 320-acre farm. An unpaved drive leads east to the house from U.S. Route 301, which is the western boundary of the property. (The historic access to the house was from the old road to the east.) The drive ends just east of the house in a circle which encloses a large evergreen tree; a short distance northeast of the circle is a champion holly. There are several large old maples to the north and west of the house.

The immediate grounds of the house are bounded by a rail fence in the north and west, and a split rail (snake) fence on the south; the fields outside these boundaries are devoted to sheep grazing. On the sloping ground in the field to the north is a twentieth century smoke house, gable-roofed with concrete block foundation. It has replaced an older smoke house which stood on a brick foundation still visible in the yard west of the house. Directly west of the house is a small square herb garden which marks the spot where an ice house once stood.

Notes

1 During restoration work in the 1970's, the mantel was removed from the south bedroom and installed in the dining room, the only room from which the mantel was missing. A new mantel was made for the south bedroom, identical to the other three.

2 In the early twentieth century, a rear shed porch on the north facade of the wing had been enclosed to form a kitchen. This enclosed porch was removed during the restoration work of the 1970's, and the concrete stoop was constructed at that time.



WOODSTOCK
PG #82A-13

1" = 8'

sgpearl 7/86

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM
Statement of Significance (continued)

Survey No. P.G. #82A-13

Section 8 Page 2

The new house was typical of small plantation houses of the mid-nineteenth century; it consisted of a side stairhall and double parlors, warmed by fireplaces on the exterior wall. The trim of the house was plain, but handsome, Greek Revival style, with broken field moldings, and carved "pillow" projections highlighting the wooden mantels. A pre-existing kitchen building, with boxed staircase and sleeping loft above, was put to use by Calvert; it stood 15 feet from his new dwelling.

Washington Calvert lived only a short time in this house. His wife died in 1857, and in 1860 he sold his entire farm (220 acres of Timberly and 100 adjoining acres of Mt. Airy) to James Beall Belt, retired Clerk of the County Court. Calvert remarried and (apparently) left Prince George's County.⁴

James Beall Belt had served as Clerk of the Court from 1838 to 1851. He owned a house and lot in Upper Marlboro where he resided, and also a store house, granary and office where he operated a mercantile business. His wife had died in 1859, and in the following year he moved with his son, John W. Belt, into Washington Calvert's house on Timberly which he renamed Woodstock. Belt continued to operate the granary, store house and office in Upper Marlboro, trading as James B. Belt and Son.⁵

After the Civil War, Belt fell into financial difficulties; he mortgaged and remortgaged his Woodstock farm. His financial difficulties were still unresolved at the time of his death in 1882. By his will he devised all of his estate, "the farm on which I now reside called Woodstock, together with all stock, crops, utensils, machinery then upon it, also all lots in Upper Marlboro, and all interest in the mercantile business carried on under the name of James B. Belt and Son," to his son, John Williamson Belt and his wife, Mary D. Belt, for their lives, in trust for his grandson (their son), James B. Belt.⁶

In the year of his father's death, John W. Belt was appointed to his father's former position as Clerk of the Court, a position which he held until his death in 1896. He also turned over the management of his store house, granary and office in Upper Marlboro to Hamilton Hall, and moved his family from their town dwelling to his father's house at Woodstock. He was also able to settle the liens on the Woodstock property by offering it for sale (by decree of the Equity Court) and purchasing it himself. It was advertised at this time (1889) as "320 acres, the land now occupied by John W. Belt, improved by a large and comfortable dwelling house and all necessary barns and outbuildings."⁷

John W. Belt died in 1896, and was buried with his parents at Trinity Church, Upper Marlboro. His estate was administered by his brother-in-law, attorney Caleb Clarke Magruder (II), and Woodstock was conveyed to his son, James B. Belt. The younger Belt predeceased his mother, however, and con-

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM
Statement of Significance (continued)

Survey No. P.G. #82A-13


Section 8 Page 3


sequently Woodstock was devised by her will (1924) to her nephew, Caleb Clarke Magruder III. It remained Magruder's home until his death in the 1940's.⁸

When the present owners purchased Woodstock from the Magruder family in 1973, the house had stood vacant and boarded up for several years, and was in deteriorating condition. The new owners undertook major restoration work, removing the shed porch which had served as a kitchen, and installing a new kitchen in the hyphen. The house is now in excellent condition, and is a prominent and visible landmark high on a hill east of U.S. Route 301. Woodstock is a significant example of a mid-nineteenth century plantation house style of southern Prince George's County, of which only a few survive.⁹

Notes

- 1 Patents, #16:496.
- 2 Federal Direct Tax for Prince George's County, 1798.
- 3 Prince George's County Estate file #174; will PC #1:443, Wollon, J.T., and Pearl, S.G., Historic Structures Report, Buck-Wardrop House, PG #79-28; Prince George's County Deeds ON #1:467; CSM #3:345,346; Prince George's County Marriage Licenses; Census for Prince George's County, 1840, 1850.
- 4 Prince George's County Deeds CSM #3:366; Stones and Bones, Cemetery Records of Prince George's County, Maryland, 1984, p. 29.
- 5 Prince George's County Court Records March 28, 1838; Prince George's County Tax Assessments, 1830's-1860's; Stones and Bones, p. 118.
- 6 Prince George's County Deed WAJ #2:585 (mortgage); Prince George's County Will WAJ Jr. #1:257.
- 7 Prince George's County Equity #1794; Prince George's County Deed JWB #12:742, 744.
- 8 Stones and Bones, p. 119; Prince George's County Estate File #1633, Prince George's County Deed JB #1:393; Prince George's County Will WTD #1:35.
- 9 Prince George's County Deed #4245:414. Recent survey work in Prince George's County has identified only two other buildings of similar plan: Bellevue (84-20), and the Turner House (87B-5). To each of these houses there is attached a lower kitchen wing which partially covers the exterior brick chimneys. In the case of the Turner House, the kitchen is a considerably later addition. Four other mid-nineteenth century dwellings [Buena Vista (70-17), Solitude (77-5), the Nourse House (77-11), and the Coffren House (86A-10)] are similar to Woodstock, but have interior chimneys and/or alterations which have significantly changed the lines of the building.







PG#82A-13

Woodstock

Prince George's County, MD

Susan G. Pearl

April 1986

Southwest 3/4 elevation

Neg: Md. Hist. Trust, Annapolis, MD



PG#82A-13

Woodstock

Prince George's County, MD.

Susan G. Pearl

April 1986

Southeast $3/4$ elevation

Neg: Md. Hist. Trust, Annapolis, MD



PG#82A-13

Woodstock
Prince George's County, MD
Susan G. Pearl
April 1986
South elevation of main block
Neg: Md. Hist. Trust, Annapolis, MD



PG#82A-13

Woodstock
Prince George's County, MD.
Susan G. Pearl
April 1986
Northeast 3/4 elevation
Neg: Md. Hist. Trust, Annapolis, MD



PG#82A-13

Woodstock
Prince George's County, MD
Susan G. Pearl
April 1986
Northwest 3/4 elevation
Neg: Md. Hist. trust, Annapolis, MD.



PG#82A-13

Woodstock

Prince George's County, MD

Susan G. Pearl

April 1986

West elevation

Neg: Md. Hist. Trust, Annapolis, MD



PG#82A-13

Woodstock
Prince George's County, MD.
Susan G. Pearl
May 1986
Stairhall, from west
Neg: Md. Hist. Trust, Annapolis, MD.



PG#82A-13

Woodstock


Prince George's County, MD

Susan G. Pearl

May 1986

Staircase detail

Neg: Md. Hist. Trust, Annapolis, MD



PG#82A-13

Woodstock
Prince George's County, MD
Susan G. Pearl
May 1986
South entrance, interior
Neg: MD Hist. Trust, Annapolis, MD



PG#82A-13

Woodstock

Prince George's County, MD

Susan G. Pearl

May 1986

Interior trim, door to south parlor

Neg: MD Hist. Trust, Annapolis



PG#82A-13

Woodstock
Prince George's County, Md.
Susan G. Pearl
May 1986
Mantel, West parlor
Neg: Md. Hist. Trust, Annapolis, MD.



PG#82A-13

Woodstock

Prince George's County, MD

Susan G. Pearl

May 1986

Siding, door, old kitchen

Neg: Md. Hist. Trust, Annapolis, MD

4245 415
J. R. McCrone, Jr., Inc.
200-400

J. R. McCrone, Jr., Inc.

Engineers and Land Surveyors

20 RIDGELY AVENUE, ANNAPOLIS, MARYLAND 21401
Annapolis - 267-8621 - Baltimore - 267-8531 - Washington - 261-2605

June 29, 1973

REPLY TO Annapolis

SCHEDULE "A"
DESCRIPTION OF 5.0001 ACRES+
PART OF THE MITTIE H. MAGRUDER PROPERTY
LOCATED ON THE EAST SIDE OF U.S. 301
15TH DISTRICT PRINCE GEORGES COUNTY, MARYLAND

BEGINNING for the same at an iron pipe set in the eastern right-of-way of U.S. 301 (250' wide) said pipe being further located as being the following courses and distances from the intersection of said eastern right-of-way and the 39th line or North 61° 28' 29" West 1865.95 foot line of the Fred Spinks, et ux., property as recorded among the Land Records of Prince Georges County, Maryland in Liber 2263, folio 382, said line being a boundary between the said Spinks property and the property of Mittie H. Magruder as recorded among the Land Records of Prince Georges County, Maryland in Liber 1147, folio 491; with the said eastern right-of-way of U.S. 301 North 24° 18' 34" East 8.14 feet to a point of curvature, thence with the arc of a curve to the left 1211.94 feet, having a radius of 14499.95 feet and being scribed by a chord North 21° 54' 54" East 1211.58 feet to a point of tangency, North 19° 31' 14" East 492.21 feet to an iron pipe set, said point being the aforementioned point of beginning;

THENCE leaving said place of beginning so fixed and binding with the said eastern right-of-way of U.S. 301 North 19° 31' 14" East 124.49 feet to an iron pipe set;

Officers
President
J. R. McCrone, Jr., Inc.
Vice President
J. R. McCrone, Jr., Inc.
Surveying Associates
DAVID C. BERRY, P.E.
THOMAS D. BUCKNER, P.E.
DAVID FORTY, P.E.
CHRISTIE GILL, P.E.

Branch Offices
P. O. BOX 20
PRINCE GEORGES, MD. 20582
204-0700
P. O. BOX 207
MOUNTAIN VIEW, MD. 20854
476-0200
IN GUNNERY SQUARE
COTTON, MD. 20759
204-0200
ONE EIGHT EIGHT
CHESAPEAKE, MD. 20540
770-0270
TRAFFIC, MD. 20777
476-0200

4245 416
DESCRIPTION OF 5.0001 ACRES
PART OF THE MITTIE H. MAGRUDER PROPERTY

PAGE 2

THENCE leaving said eastern right-of-way of U.S. 301 and running for new lines of division through the abovementioned land of Mittie H. Magruder the following four (4) courses and distances: South $74^{\circ} 26' 33''$ East 592.70 feet to an iron pipe set, South $19^{\circ} 31' 14''$ West 441.27 feet to an iron pipe set, North $66^{\circ} 33' 59''$ West 512.48 feet to an iron pipe set, and North $19^{\circ} 31' 14''$ East 240.84 feet, also with the end of a 60 foot right-of-way to an iron pipe set on the northern side of the said 60 foot right-of-way, for use in common with the herein described property and the remainder of the said Magruder property;

THENCE with the northern side of the said 60' right-of-way North $76^{\circ} 28' 46''$ West 80.00 feet to the place of beginning.

CONTAINING 5.0001 acres, more or less, as surveyed by J. R. McCrone, Jr., Inc., Registered Professional Engineers and Land Surveyors in June 1973.

BEING a part of the property of Mittie H. Magruder, as recorded among the Land Records of Prince Georges County, Maryland in Liber 1147, folio 491.

(11/5/79)

PRINCE GEORGE'S COUNTY
HISTORIC SITES SUMMARY SHEET

P.G. County Survey # 82A-13 Date ca. 1850 and earlier
Building Name Woodstock
Location Crain Highway (#301), Upper Marlboro, Md.
Open to Public yes x no

Woodstock is a large, frame, two-part house. The larger part has two stories plus attic and cellar, has a gable roof, and is three bays wide with the main entrance in the third bay. There are two exterior chimneys at the west gable end. There is a one-story three-bay porch across the front. All of the windows have shutters. The smaller part is one-and-one-half stories high, and has a steep gable roof pierced by two dormers. A large exterior chimney is at the west gable end. The south facade is five bays wide with doors in the second and fourth bays. The roof line extends to form a one-story porch across the south front. Construction details in the upper floor indicate that the west half of the wing was built earlier than the section, which joins it to the large two-story part of the house.

Woodstock is located on the tract patented as Timberly, part of which became a part of the huge Mt. Airy estate. James Beall Belt, clerk of the Circuit Court, purchased the property in 1850 and is believed to have built the large part of the house as an addition to the much older one-and-one-half story section. No proof of this has been found. Belt's son, John W., was also clerk of the Circuit Court and continued to live there as did his son.

The larger part of Woodstock is typical of many houses built in this area during the early to mid 1800's.

MARYLAND HISTORICAL TRUST

P.G. #82A-13

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

Woodstock

AND/OR COMMON

2 LOCATION

STREET & NUMBER

Crain Highway

CITY, TOWN

Upper Marlboro

VICINITY OF

CONGRESSIONAL DISTRICT

4th

STATE

Maryland

P.G.

COUNTY

3 CLASSIFICATION

CATEGORY

- ☐ DISTRICT
- ☒ BUILDING(S)
- ☐ STRUCTURE
- ☐ SITE
- ☐ OBJECT

OWNERSHIP

- ☐ PUBLIC
- ☒ PRIVATE
- ☐ BOTH

PUBLIC ACQUISITION

- ☐ IN PROCESS
- ☐ BEING CONSIDERED

STATUS

- ☒ OCCUPIED
- ☐ UNOCCUPIED
- ☐ WORK IN PROGRESS
- ☐ ACCESSIBLE
- ☐ YES: RESTRICTED
- ☐ YES: UNRESTRICTED
- ☒ NO

PRESENT USE

- ☐ AGRICULTURE
- ☐ MUSEUM
- ☐ COMMERCIAL
- ☐ PARK
- ☐ EDUCATIONAL
- ☒ PRIVATE RESIDENCE
- ☐ ENTERTAINMENT
- ☐ RELIGIOUS
- ☐ GOVERNMENT
- ☐ SCIENTIFIC
- ☐ INDUSTRIAL
- ☐ TRANSPORTATION
- ☐ MILITARY
- ☐ OTHER

4 OWNER OF PROPERTY

NAME

Mr. & Mrs. Eugene Couser

Telephone #: 952-0287

STREET & NUMBER

Crain Highway

CITY, TOWN

Upper Marlboro

VICINITY OF

Maryland

STATE, zip code

20870

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,

REGISTRY OF DEEDS, ETC.

P.G. County Courthouse

Liber #: 4245

Folio #: 414

STREET & NUMBER

Main Street

CITY, TOWN

Upper Marlboro

STATE

Md.

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

P. G. Survey

(not in HABS)

DATE

1974

☐ FEDERAL ☐ STATE ☒ COUNTY ☐ LOCAL

DEPOSITORY FOR
SURVEY RECORDS

Calvert Mansion, 4811 Riverdale Road, Riverdale, Md.

CITY, TOWN

STATE

7 DESCRIPTION

PG:82A-13

CONDITION

☒ EXCELLENT
☐ GOOD
☐ FAIR

☐ DETERIORATED
☐ RUINS
☐ UNEXPOSED

CHECK ONE

☐ UNALTERED
☒ ALTERED

CHECK ONE

☒ ORIGINAL SITE

☐ MOVED

DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Woodstock is located high above the highway on the east side of Crain Highway (#301) about 5 miles south of Upper Marlboro. It is a large, frame, two-part house which faces south. The larger part is two stories with attic and cellar, has a gable roof, and is three bays wide with the main entrance in the third bay. There are two exterior chimneys at the west gable end. There is a one-story three-bay porch across the front. All of the windows have shutters. The smaller part is one-and-one-half stories high, and has a steep gable roof pierced by two dormers. A large exterior chimney is at the west gable end. The south facade is five bays wide with doors in the second and fourth bays. The roof line extends to form a one-story porch across the south front. Construction details in the upper floor indicate that the west half of the wing was built earlier than the east section which joins ^{it to} the large two-story part of the house.

There are several very large old trees in the yard.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

PG:82A-13

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION	
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE	
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE	
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER	
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION	
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)	
		<input type="checkbox"/> INVENTION		<input checked="" type="checkbox"/> local history	

SPECIFIC DATES circa 1850 and earlier BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

Woodstock is located on the tract patented as Timberly, part of which became a part of the huge Mt. Airy estate. James Beall Belt, clerk of the Circuit Court purchased the property in 1850 and is believed to have built the large part of the house as an addition to the much older one-and-one-half story section. No proof of this has been found. Belt's son, John W., was also the clerk of the Circuit Court and continued to live there as did his son.

The larger part of Woodstock is typical of many houses built in the area during the early to mid 1800's.

CONTINUE ON SEPARATE SHEET IF NECESSARY

9 MAJOR BIBLIOGRAPHICAL REFERENCES

P.G. County Land Records

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE

COUNTY

STATE

COUNTY

11 FORM PREPARED BY

NAME / TITLE

Margaret W. Cook

ORGANIZATION

P.G. Historical & Cultural Trust

DATE

October 1979

STREET & NUMBER

Calvert Mansion, 4811 Riverdale Road

TELEPHONE

779-2011

CITY OR TOWN


Riverdale, Md.

STATE

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438



1703755304
A.A. 22A-13

MARYLAND HISTORICAL TRUST WORKSHEET

NOMINATION FORM for the NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

SEE INSTRUCTIONS

1. NAME				
COMMON:				
AND/OR HISTORIC: Woodstock				
2. LOCATION				
STREET AND NUMBER: Rte. 301				
CITY OR TOWN: Upper Marlboro				
STATE: Maryland			COUNTY: Prince George's	
3. CLASSIFICATION				
CATEGORY (Check One)		OWNERSHIP		STATUS
<input type="checkbox"/> District <input checked="" type="checkbox"/> Building <input type="checkbox"/> Site <input type="checkbox"/> Structure <input type="checkbox"/> Object		<input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both		<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress
		Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered		ACCESSIBLE TO THE PUBLIC Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No
PRESENT USE (Check One or More as Appropriate)				
<input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment		<input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum		<input type="checkbox"/> Park <input checked="" type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific
		<input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify) _____		<input type="checkbox"/> Comments _____
4. OWNER OF PROPERTY				
OWNER'S NAME: E. A. Couser				
STREET AND NUMBER: Rte. 301				
CITY OR TOWN: Upper Marlboro			STATE: Maryland	
5. LOCATION OF LEGAL DESCRIPTION				
COURTHOUSE, REGISTRY OF DEEDS, ETC.: Prince George's County Courthouse				
STREET AND NUMBER:				
CITY OR TOWN: Upper Marlboro			STATE: Maryland	
Title Reference of Current Deed (Book & Pg. #):				
6. REPRESENTATION IN EXISTING SURVEYS				
TITLE OF SURVEY: Historic Sites in the Bi-County Region				
DATE OF SURVEY: 1969 <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> County <input type="checkbox"/> Local				
DEPOSITORY FOR SURVEY RECORDS: M-NCPPC				
STREET AND NUMBER: 8787 Georgia Avenue				
CITY OR TOWN: Silver Spring, M			STATE: Maryland	

7. DESCRIPTION

CONDITION	(Check One)					
	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site		

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

The house is a frame building built in two sections. The main (east) end is three bays with the doorway in the east bay. There are neither sidelights nor transom lights. The windows are 6/6 double hung sash. A one story porch with square, bracketed posts extends across the facade. There is a boxed cornice with neither bed nor crown moulding. On the west end, there are two external chimneys with two story bases and stepped weatherings to the stacks. The south stack has been widened by a length of two stretchers.

On the west end there is a story and a half wing that is probably older. It is frame with a facade of five irregular bays, the second bay from either end being a doorway. The windows are also 6/6 double hung sash. On the west end there is an external chimney with stepped weatherings and a free standing stack. On the south facade there are two dormer windows with 6/6 double hung sash.

SEE INSTRUCTIONS

9. SIGNIFICANCE**PERIOD (Check One or More as Appropriate)**

- | | | | |
|--|---------------------------------------|--|---------------------------------------|
| <input type="checkbox"/> Pre-Columbian | <input type="checkbox"/> 16th Century | <input type="checkbox"/> 18th Century | <input type="checkbox"/> 20th Century |
| <input type="checkbox"/> 15th Century | <input type="checkbox"/> 17th Century | <input checked="" type="checkbox"/> 19th Century | |

SPECIFIC DATE(S) (If Applicable and Known)**AREAS OF SIGNIFICANCE (Check One or More as Appropriate)**

- | | | | |
|---|--------------------------------------|--|--|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Philosophy | <input type="checkbox"/> Other (Specify) |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | <input type="checkbox"/> Science | _____ |
| <input type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Sculpture | _____ |
| <input type="checkbox"/> Architecture | <input type="checkbox"/> Landscape | <input type="checkbox"/> Social/Humanitarian | _____ |
| <input type="checkbox"/> Art | <input type="checkbox"/> Literature | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Military | <input type="checkbox"/> Transportation | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Music | | |
| <input type="checkbox"/> Conservation | | | |

STATEMENT OF SIGNIFICANCE

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			OR	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

Acreage Justification:

SEE INSTRUCTIONS

11. FORM PREPARED BY

NAME AND TITLE:

Christopher Owens, Park Historian

ORGANIZATION

M-NCPPC

DATE

24 Sept 74

STREET AND NUMBER:

8787 Georgia Avenue

CITY OR TOWN:

Silver Spring

STATE

Maryland


12.


State Liaison Officer Review: (Office Use Only)

Significance of this property is:

National ☐ State ☐ Local ☐

Signature _____





WOODSTOCK


PG:82A-13

Prince George's County
Maryland

first floor plan, 1986

scale 1"=8'

drawn by Susan G. Pearl



82A-13
1" = 200'

204 c. Snake house

Woodstock

WOODSTOCK
PG#82A-13
1" = 200'



PG: 82A-13

Click here for a plain text ADA compliant screen.



Maryland Department of Assessments and Taxation
PRINCE GEORGE'S COUNTY
Real Property Data Search

[Go Back](#)
[View Map](#)
[New Search](#)

Account Identifier: District - 15 Account Number - 1724996

Owner Information

Owner Name: RILEY, ANNE T Use: RESIDENTIAL
Principal Residence: YES
Mailing Address: 8706 CRAIN HWY Deed Reference: 1) /11133/ 701
UPPER MARLBORO MD 20772-5161 2)

Location & Structure Information

Premises Address 8706 SE CRAIN HWY Zoning RA Legal Description HOMESITE
UPPER MARLBORO 20772 (AG# 1725001)

Map	Grid	Parcel	Sub District	Subdivision	Section	Block	Lot	Group	Plat No:
118	E2	106						81	Plat Ref:
Special Tax Areas			Town Ad Valorem Tax Class	08					
Primary Structure Built			Enclosed Area	Property Land Area			County Use		
1800			2,977 SF	1.00 AC			003		
Stories		Basement		Type			Exterior		
2 1/2		NO		STANDARD UNIT			FRAME		

Value Information

	Base Value	Value As Of	Phase-in Assessments	
		01/01/2002	As Of	As Of
			07/01/2003	07/01/2004
Land:	50,000	55,000		
Improvements:	133,340	162,530		
Total:	183,340	217,530	206,132	217,530
Preferential Land:	0	0	0	0

Transfer Information

Seller: COUSER, EUGENE A & MARY S Date: 11/25/1996 Price: \$240,000
Type: MULT ACCTS ARMS-LENGTH Deed1: /11133/ 701 Deed2:
Seller: MAGRUDER, MITTIE H Date: 07/09/1973 Price: \$0
Type: UNKNOWN Deed1: / 4245/ 414 Deed2:
Seller: Date: Price:
Type: Deed1: Deed2:

Exemption Information

Partial Exempt Assessments	Class	07/01/2003	07/01/2004
County	000	0	0
State	000	0	0
Municipal	000	0	0

Tax Exempt: NO
Exempt Class:

Special Tax Recapture:


* NONE *




Maryland Department of Assessments and Taxation
PRINCE GEORGE'S COUNTY
Real Property Data Search


[Go Back](#)
[View Map](#)
[New Search](#)

District - 15 Account Number - 1724996



Property maps provided courtesy of the Maryland Department of Planning ©2001 - 2002.
For more information on electronic mapping applications, visit the Maryland Department of Planning
web site at www.mdp.state.md.us/webcom/index.html





20772


PG: 82A-13
ADC of Alexandria, Inc., 1993

Joins Map 33

MD GRID 860,000 FT

© ADC OF ALEXANDRIA, INC.

31



Federal Spring Recreation Center PG: 82A-13

el Pit

HIGHWAY

CRAIN

Horse Tavern

ROAD

CHEW

301

Branch

Substa

301

Douglas High Sch



Charles Gravel Pit

Branch

Croom Station

Marlton Rec Center

CONRAIL

Branch

PG: 82A-13

Woodstock

Upper Marlboro Quad, 1965, PR 1978

HILL

TRUMP

St Marys Ch

CROOM AIRPORT RD

aryville

Old House Cr



NAME WOODSTOCK

PG: 82A-13

LOCATION Rt 301 ROSARYVILLE, Md.

FACADE SE

PHOTO TAKEN 9/24/74 MDWYER



NAME WOODSTOCK

PG: 82A-13

LOCATION Rt 301 ROSARYVILLE, Md

FACADE W

PHOTO TAKEN 9/24/74 MDWYER



NAME WOODSTOCK

PF: 87 A-13

LOCATION Rt 301 ROSARY VILLE, Md.

FACADE W WING - S FACADE

PHOTO TAKEN 9/24/74 MDWYER